

Sector	Drinking Water
Name of the Project	Providing 24x7 Pressurized Continuous water Supply Scheme to balance 15 Zones of Ballari City Corporation Ballari
Proposal submitted by	Deputy Commissioner, Ballari
Total Project Cost	INR 270.64 Cr.
Coverage	15 Zones of Ballari City Corporation Ballari
Project Duration	3 Years
Project Implementing Agency	KUWS & DB, Ballari Division
Objective	To provide 24x7 Pressurised Continuous water Supply to Ballari city
Output	<ol style="list-style-type: none"> 1) 75 mm to 200 mm dia HDPE pipe line- 398.878 Km. 2) 250 to 400 mm dia DI Pipe line - 22.22 Km. 3) Construction of 10 LL OHT - 15 mtr staging - 3 Nos. 4) Construction of 15 LL OHT- 12 mtr staging - 3 Nos. 5) Construction of 15 LL OHT- 15 mtr staging - 9 Nos. 6) Construction of 5 LL OHT- 15 mtr staging - 1 No. 7) Providing and laying feeder mains - 11239.00 mtr length). 8) Providing HSC with Meter as 42500 Nos. 9) Supply, erection and commissioning of 10 HP Centrifugal pumps
Justification	As Per 2011 census, the population of Ballari District Head quarter was 410445. Presently (Intermediate population by 2036 is anticipated as 750000 & by 2050 is anticipated as 1012500),the population is about 450000 and the city is Spread over from South west to North east & covering geographical area of about 8447 sq kms. Hence, it is proposed to have 24X7 pressurized continuous water supply schemes to 15 zones of Ballari City.